



TYPICAL MATERIALS Permeable Paver Installs

PHILADELPHIA
WATER

phillywatersheds.org/raincheck



GEOTEXTILE LINER
6 OZ./SY NWNP

(<http://earthaidusa.com/geo-fabric.aspx>)



WATER-PROOF LINER
30 MIL POLY SHEETING

(<http://www.thepondoutlet.com/>)



DOUBLE-COATED BUTYL TAC TAPE

(<http://www.crawlspacedepot.com/>)

TYPICAL STONE AGGREGATE MATERIALS

(<http://www.yorkbuilding.com/aggregate-products/stone/>)



ASTM NO. 2 STONE
2 - 3 INCH AVERAGE



ASTM NO. 57 STONE
3/4 - 1 INCH AVERAGE



ASTM NO. 8 STONE
3/8 - 1/2 INCH AVERAGE



PEA GRAVEL
1/8 - 3/8 INCH AVERAGE

TYPICAL PAVER MATERIALS

(<http://norristownbrick-ephenry.com/driveways-gallery>)



Note: These materials are not requirements for Rain Check installations. They are meant to provide contractors with different options for permeable paver installations. All installations must meet ICPI requirements for permeable paver installations.